



FILE NO: 90.554UK  
 DATE: Feb. 22, 2011  
 SUPERSEDES: New  
 DATE: New

# IPS Controller 9500

# SUBMITTAL

JOB: _____	REPRESENTATIVE: _____
_____	_____
ENGINEER: _____	ORDER NO: _____ DATE: _____
CONTRACTOR: _____	SUBMITTED BY: _____ DATE: _____
	APPROVED BY: _____ DATE: _____

SYSTEM LAYOUT / CONFIGURATION	
Number of variable pumps being controlled	_____ (Specify 1 to 6)
Number of remote zone Differential Pressure signals	_____ (Specify 1 to 18)

IPS CONTROLLER 9500 VARIANT				
Model	Input Zone Capability	Output Pump Control Capability	Select whether Chillers/Boilers are to be sequenced by IPS Controller 9500 Models: 9501-9503 NO sequencing Models: 9511-9513 WITH sequencing	
IPS Controller 9501 / 9511	up to 6 Zones	up to 6 pumps & 5 chillers/boilers	<input type="checkbox"/> IPS9501 <input type="checkbox"/> IPS9511	<input type="checkbox"/> Sequence chillers/boilers?
IPS Controller 9502 / 9512	up to 12 Zones	up to 6 pumps & 5 chillers/boilers	<input type="checkbox"/> IPS9502 <input type="checkbox"/> IPS9512	<input type="checkbox"/> Sequence chillers/boilers?
IPS Controller 9503 / 9513	up to 18 Zones	up to 6 pumps & 5 chillers/boilers	<input type="checkbox"/> IPS9503 <input type="checkbox"/> IPS9513	<input type="checkbox"/> Sequence chillers/boilers?

- | STANDARD FUNCTIONALITY and CONSTRUCTION  |
|--|
| <ul style="list-style-type: none"> <li>A large-sized (10.4") touch-screen operator interface</li> <li>On-screen menu driven operator interface</li> <li>Manual or automatic system control (H-O-A selection)</li> <li>Remote or local start/stop mode of operation</li> <li>Field and factory password security</li> <li>Alarm and event logging of 2000 events</li> <li>Data trending with display screen</li> <li>PID control loop, adjustable</li> <li>CE Marked with EMC and LVD compliance</li> <li>Internal circuit breaker protection</li> <li>Automatic or manual pump alternation</li> <li>Remote start/stop of variable speed primary pumps by chiller, boiler or BMS</li> <li>Best Efficiency Point (BEP) staging</li> <li>Wire-to-water efficiency monitoring and staging</li> <li>4 standard alarms: (1) drive, motor overload or pump failure (2) system fault (3) zone signal fault (4) primary pump fatal alarm</li> <li>Separate operating status display of primary pump status, pump speed(s) and drive status</li> <li>Digital inputs for pump differential pressure switches on all variable speed primary pumps</li> <li>Output for remote alarm/horn signal</li> <li>Input for silencer of remote alarm/horn</li> <li>Standard serial communication between IPS Controller and VFD's</li> <li>Separate input screen for DP, flow, temperature and kW sensors</li> <li>Separate input screens for differential pressure sensor setpoint and operating range (psi or feet)</li> <li>Logic outputs for VFD automatic bypass control</li> <li>Logic outputs for chiller/boiler 2-way automatic ON/OFF isolation valves</li> <li>Logic output for chiller/boiler 2-way automatic modulating bypass valve</li> <li>Separate status screen of remote zone signals, zone faults, zone setpoint and active control zone</li> <li>Embedded logic to prevent hunting, pump flow surge and motor overloading</li> <li>Multi-color schematic active display of mechanical room hydronic circuit indicating operating status</li> <li>Manual control screen for fixed speed, bypass or selected variable speed settings</li> <li>IP54 Enclosure with Door Interlocked Isolator</li> <li>Diagnostic test of CPU, RAM and Flash memory</li> </ul> |

DIMENSIONS and WEIGHTS				
Model	Width	Height	Depth	Weight
IPS Controller 9501 / 9502 / 9511	600mm	800mm	250mm	43 KG
IPS Controller 9503 / 9512 / 9513				52 KG

POWER SUPPLY		
Volts	Frequency	Phase
<input type="checkbox"/> 240 Vac	50 Hz	single

ENCLOSURE DETAILS
<input type="checkbox"/> IP54
<input type="checkbox"/> IP55
<input type="checkbox"/> IP65

- | OPTIONS and ACCESSORIES   |
|---|
| <input type="checkbox"/> A serial communications port for communication with a Building Management System (standard communication options included with basic system are Modbus, LonWorks, Trend, Johnson Controls Metasys N2 and pLAN) |
| <input type="checkbox"/> Serial communications port to receive full information from the variable speed drives (VFD's)  |
| <input type="checkbox"/> Optional communications gateways for BACnet and Webgate (TCP/IP)   |
| <input type="checkbox"/> Armstrong shall enter the project specific field enter parameters  |
| <input type="checkbox"/> Telephone communications modem and port  |
| <input type="checkbox"/> Flash memory card expandable to 6 MB   |
| End-of-curve on primary pumps using <input type="checkbox"/> DP sensor or <input type="checkbox"/> Flow sensor  |

<b>Armstrong Integrated Limited</b> Wenlock Way Manchester United Kingdom, M12 5JL T: +44 (0) 8444 145 145 F: +44 (0) 8444 145 146	<b>S. A. Armstrong Limited</b> 23 Bertrand Avenue Toronto, Ontario Canada, M1L 2P3 T: 416-755-2291 F: 416-759-9101
---	---